

## **Corrigendum**

Please refer to this office Tender No. NRCG/5(125)/2016-17/APEDA NRL (with Tender ID 2016\_DARE\_158107\_1). In this connection, it is to inform you that specifications for construction of walking cold storage should be considered as follows-

### **Specifications for Walk – In Cold Storage**

- Size of the cold storage – appx 80 sq feet area and height of 8 feet
- Temperature: 0 - 40<sup>0</sup>C ( ±2<sup>0</sup>C )
- Refrigeration system should be of a standard make like Voltas, Carries, Blue Star, Bitzer, Emerson etc.
- Pull down time should be of 18-20 Hrs
- Humidity: 75-80 % (±5%) at 26<sup>0</sup>C
- Material for insulation – PUF
- Thickness – 60 mm for wall and ceiling
- Lamination for walls / ceiling – SS inside, powder coated GI for outside
- Flooring type –PUF slab (thickness 60 mm) with PCC Kotta
- Single door, flush type swing door with 60 mm insulation
- Door lamination- SS inside, PP outside
- Should be provided with Racks (Quantity – 4 Nos. of 5' x 2'x 6' (lxdxh) dimensions with 3 shelves) make up of 18 gauge GI with corrosion powder coating.
- Each shelf should be illuminated with LED light with the following specification- 4x36W T5 florescent light. Timer for controlling light duration should duration should be provided for each rack.
- Scope of work also include the supply of good quality water to humidifier from water tank ( *including plumbing, consumables and water purifier*)
- Interested firms are requested to visit the site before submitting the tender.

**Yours faithfully**

**Sd/-  
Assistant Administrative Officer**

